

ALL REQUIRED DOCUMENTS MUST BE IN PLACE BEFORE YOU WILL BE GIVEN THE OPPORTUNITY TO BID ON THE FOLLOWING:

NORTHLAND NEIGHBORHOODS, INC.
4420 NE Chouteau Trafficway
KANSAS CITY, MO 64117

Office: 816-454-2000

Fax: 816-454-1747

bids@nni.org; lori_morgan@nni.org

July 23, 2015

NOTICE OF CONTRACTING OPPORTUNITY

Your written bid must be itemized, signed and received by NNI in a sealed envelope NO LATER THAN JULY 29, 2015 @ 2:00PM. All bids must be valid for 60 days from Bid Date.

The work scope is attached to this notice. All questions or concerns must be submitted as RFI's to bids@nni.org.

General Project Notes:

All Contractors submitting proposals for this work shall first examine the site and all conditions therein. **All proposals shall take into consideration each and every such condition that may affect the work to be performed.**

The submission of a bid will signify to NNI that the Bidder has fully examined the site, understands the work scope and NNI general requirements. All bids must include: scope of work, location of project, client number, and signature.

In projects where paint will be disturbed, Contractor must provide a certificate that Contractor is certified to conduct lead-based paint renovation, repair, and painting activities. In such cases Contractor must use Lead Base Paint (LBP) Safe Work Practices.

While care has been exercised in verification of dimensions and preparation of work scope, it shall be the responsibility of the Contractor to recheck and verify all dimensions and conditions before fabricating or installing materials. All apparent discrepancies shall be promptly reported to NNI.

If your bid is Selected:

A Notice To Proceed (NTP) will be issued for the project. Please sign and return the NTP to NNI. **You MUST notify NNI and client prior to start date.**

It shall be assumed that once a Contractor starts work, all conditions of NNI have been accepted and the Contractor shall then be held fully responsible for any defects thus occurring from the Contractor's work.

Project site:

4400 Campbell Avenue

NNI GENERAL REQUIREMENTS

Exhibit to Work Scope

VERIFY QUANTITIES/MEASUREMENTS

All quantities stated in the attached work scope for this address are for the Contractor's convenience and must be verified by the contractor at a mandatory site inspection prior to bid submission. Discrepancies in quantities found by the Contractor must be communicated to a NNI Housing Associate prior to the submission of a bid. Claims for additional funds due to discrepancies in quantities shall not be honored if submitted after the bid submission.

NEW MATERIALS REQUIRED

All materials used in connection with this work scope are to be new, of first quality and without defects – unless stated otherwise or pre-approved by Owner and Northland Neighborhoods, Inc.

All materials and equipment used for this project shall be adequately inspected and tested in accordance with accepted standards. All materials and equipment for this project shall be installed, applied, or erected in strict accordance with manufacturer's trade association requirements unless technical specifications exceed these requirements. In such circumstances technical specifications shall prevail.

SCOPE OF WORK

Contractor shall follow the work scope and shall not do any extra work, provide extra equipment or supplies, or perform any services resulting in any charges to NNI over the agreement amount. Contact NNI if conditions indicate a revision of the work scope is needed. Any changes to the work scope will only be made through written authorization by NNI.

WORKMANSHIP STANDARDS

All work shall be performed by mechanics both licensed and skilled in their particular trade as well as the tasks assigned to them. Workers shall protect all surfaces as long as required to eliminate damage. All labor and material shall comply with the current Kansas City, Missouri Building and Rehabilitation Codes.

All homeowners will be treated with the utmost respect by all.

1 YEAR GENERAL WARRANTY

Contractor shall remedy any defect due to faulty material or workmanship and pay for all damage to other work resulting therefrom, which appear within one year from final payment. Contractor shall furnish owner with all manufacturers' and suppliers' written warranties covering items furnished under this contract, prior to release of the final payment.

FINAL CLEAN

Remove from site all construction materials, tools and debris. Sweep clean all exterior work areas. Vacuum all interior work areas, removing all visible dust, stains, labels and tags. Clean all windows referenced in specifications. All refuse and debris resulting from this work shall be removed from the site and legally dumped at a licensed landfill.

PERMITS

Contractor will obtain any and all necessary permits to complete the project. NNI will require copies of the City's passing inspection report.

LEAD-SPECIFIC LAWS, RULES, REGULATIONS & GUIDELINES

LBP testing or other testing may be required for this project.

Contractor's work will be expected to pass required inspections and testing. If a test or inspection fails, Contractor will pay the cost of additional testing and inspection.

The execution of this work shall comply with all applicable federal, state and local laws, rules, regulations, and guidelines for lead dust environments, including but not limited to: 24 CFR.

SPECS BY LOCATION/TRADE

7/23/2015

Pre-Bid Site Visit: _____
 Bidding Open Date: _____
 Bidding Close Date: _____
 Initial: _____

Case Number: Encore
 Project Manager: Monte Rodgers
 Phone: 816-454-3236

Address: 4400 NE Campbell Avenue

Unit: Revised 7/23/15

Location: 1 - Exterior

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 10 Carpentry					
2330	DECKING--CUSTOM Using lead safe practices,remove existing lower deck at rear entrance (approx. 5' x 8') and dispose of properly. Install new concrete piers, reframe new deck same dlmentions as old deck, using all pressure treated lumber. Deck must be built to Kansas City building codes,piers,tread height,rail height etc (if applicable). *Remove and reinstall existing deck railings. Provide new 6 mil vapor barrier under new deck. Provide Galvanized L- Flashing at all siding/decking intersections.*	40.00	SF	_____	_____
2995	WINDOW--VINYL CUSTOM 1. Using Lead Safe Work Practices, remove all existing wood windows and dispose of properly. 2. Field measure, order and install a vinyl, double hung, Low E, Energy Star Coronet Window or equal. All windows will be custom made. 3. Replace any deteriorated, broken, rotted or missing materials associated with the window cavity, framing, and trim prior to installation of window. 4. Install one frosted window in bathroom if approved by owner (if applicable). 5. Windows are to be silicone or caulked and installed according to manufacturer recommendations. 6. All gaps and cracks will be foam filled for additional insulation. 7. Repair all damage caused by the installation of the windows to include but not limited to the exterior and interior trim. 8. Installation shall pass any testing required, including LBP testing. *Install 2 new 1x2 pine sill nosings at left front window and right side window. Prime and paint with exterior acrylic latex in color to match existing as close as possible.*	5.00	EA	_____	_____

Location Total: _____

Unit Total for 4400 NE Campbell Avenue, Unit Revised 7/23/15: _____

Address Grand Total for 4400 NE Campbell Avenue: _____

Bidder: _____